1 / 12 · Plan and Coordinate Work

Which three records do you compare to build a device count before a periodic test?

alarmladder.com · free NICET I&T FA I check

2 / 12 · Plan and Coordinate Work

Why is the panel's point list not enough on its own to count devices?

alarmladder.com · free NICET I&T FA I check

3 / 12 · Plan and Coordinate Work

You find three detectors on the point list that are not on the record drawings. What do you do?

alarmladder.com · free NICET I&T FA I check

4 / 12 · Plan and Coordinate Work

What is an orphan address?

alarmladder.com · free NICET I&T FA I check

5 / 12 · Plan and Coordinate Work

Who is your main contact for access and timing during a periodic test?

alarmladder.com · free NICET I&T FA I check

6 / 12 · Plan and Coordinate Work

Name four things to agree with the building manager before testing.

alarmladder.com · free NICET I&T FA I check

Original flashcards, never real or recalled exam questions. Not affiliated with or endorsed by NICET.

2 / 12 · Plan and Coordinate Work

It shows what the panel is programmed for, not what is on the ceiling. A removed device can leave an orphan address, and a new device may be missing from the drawings.

NFPA 72-2022 Chapter 7

alarmladder.com · free NICET I&T FA I check

1 / 12 · Plan and Coordinate Work

The record drawings, the panel's point list or programming report, and last year's inspection and test report. Then walk the building to check them against what is installed.

NFPA 72-2022 Chapter 7; 14.2

alarmladder.com · free NICET I&T FA I check

4 / 12 · Plan and Coordinate Work

A point still programmed in the panel after its device was removed. Record it as a finding so the program can be corrected.

NFPA 72-2022 14.6

alarmladder.com · free NICET I&T FA I check

3 / 12 · Plan and Coordinate Work

Confirm them on site, test them, and note on the report that the drawings need updating so the owner can have them corrected.

NFPA 72-2022 Chapter 7; 14.6

alarmladder.com · free NICET I&T FA I check

6 / 12 · Plan and Coordinate Work

Access to rooms and ceilings, when appliances may sound, who tells the occupants, and which interfaces (doors, elevators, fans) will operate.

NFPA 72-2022 14.2

alarmladder.com · free NICET I&T FA I check

5 / 12 · Plan and Coordinate Work

The owner or the building manager acting for the owner. The owner is responsible for the system.

NFPA 72-2022 14.2

alarmladder.com · free NICET I&T FA I check

Original flashcards, never real or recalled exam questions. Not affiliated with or endorsed by NICET.

7 / 12 · Plan and Coordinate Work

Why agree in advance which interfaces will operate during the test?

alarmladder.com · free NICET I&T FA I check

8 / 12 · Plan and Coordinate Work

Where are the periodic inspection and test frequencies and methods?

alarmladder.com · free NICET I&T FA I check

9 / 12 · Plan and Coordinate Work

Who decides which edition of the code applies to an existing system?

alarmladder.com · free NICET I&T FA I check

10 / 12 · Plan and Coordinate Work

The work order says annual test, but some devices are also due for another inspection. What do you do?

alarmladder.com · free NICET I&T FA I check

11 / 12 · Plan and Coordinate Work

Which section covers notifications before testing?

alarmladder.com · free NICET I&T FA I check

12 / 12 · Plan and Coordinate Work

What do you tell the supervising station before testing?

alarmladder.com · free NICET I&T FA I check

Original flashcards, never real or recalled exam questions. Not affiliated with or endorsed by NICET.

8 / 12 · Plan and Coordinate Work

In Chapter 14 of NFPA 72, mostly in its tables.

NFPA 72-2022 Chapter 14

alarmladder.com · free NICET I&T FA I check

7 / 12 · Plan and Coordinate Work

Doors closing, elevators recalling and fans stopping affect people and other trades, and the person responsible for each may need to be present.

NFPA 72-2022 14.2; Chapter 21

alarmladder.com · free NICET I&T FA I check

10 / 12 · Plan and Coordinate Work

Tell the owner before starting, so the scope can match what is due under the Chapter 14 tables.

NFPA 72-2022 Chapter 14

alarmladder.com · free NICET I&T FA I check

9 / 12 · Plan and Coordinate Work

The authority having jurisdiction, through the edition and local changes it has adopted. The newest printed edition is not automatically the one that applies.

NFPA 72-2022 14.1

alarmladder.com · free NICET I&T FA I check

12 / 12 · Plan and Coordinate Work

The account, which signals to expect, and roughly how long the test will run, so test signals are not treated as real ones.

NFPA 72-2022 14.2.4

alarmladder.com · free NICET I&T FA I check

11 / 12 · Plan and Coordinate Work

14.2.4 in NFPA 72-2022.

NFPA 72-2022 14.2.4

alarmladder.com · free NICET I&T FA I check

Original flashcards, never real or recalled exam questions. Not affiliated with or endorsed by NICET.